



- HUB Excavate for and lay concrete foundations for new Hub as per drawing 16225/22/A. Once Hub installed by FCC Sub-contractor, return to site and lay surface course as below: Surface Course - 6mm Aggregate Dense Bitumen Macadam Binder Course. Depth 25mm Area = 6m²
- Plane Footway, Depth 25mm. Dispose of Material. Place Tac Coat on area and resurface with: Surface Course - 6mm Aggregate Dense Bitumen Macadam Binder Course. Depth 25mm Area = 170m²

BASED UPON VARIOUS ORDNANCE SURVEY MAPS WITH THE PERMISSION OF THE CONTROLLER OF HM STATIONARY OFFICE. CROWN COPYRIGHT RESERVED LICENSE NUMBER LA 100023386L FLINTSHIRE COUNTY COUNCIL, COUNTY HALL, MOLD.

PRELIMINARY APPROVAL CONSTRUCTION

Ph/Rev.	Revision Details	Rev.by	Chk.by	Date



Steve Jones
 Chief Officer (Streetscene and Transportation) County Hall, Mold, CH7 6NF
 Prif Swyddog (Swyddfaethau Stryd a Thrafnidiaeth) Heolau a Sir, Yr Wyddgrug, CH7 6NF

Community Trasport Hubs 2016-17
 Ewloe - Mold Road
 Proposed Works
 Sheet 1 of 1

Flintshire County Council - Environment Directorate, County Hall I, Mold CH7 6NF			
Contact Name:	Adam Foley	Telephone:	01352 70xxxx
Drawn by:	AF	Fax No:	01352 70
Checked by:	AF	Date:	09.12.16
Scales at A1:	Drawing No:	Phase/Rev:	
1:100	16225/07	C	